

Cornerstone Vocational Training Ltd

70 Price Street, Birkenhead, CH41 3QZ

Location: 70 Price Street

GENERAL RISK ASSESSMENT

| | | |
|---|---|-------------------------------------|
| Title : Assemble interior units | Date of Assessment : 05/11/2021 | Risk Assessor : Brendan Bell |
| Risk Assessment Reference : K01 | People involved in making this assessment : Brendan Bell, Ian Jones, Learners (Students) | |
| Task/ Process : Assembling flat pack kitchen units | People at Risk : Employees, Children & Young Persons | |

Hazard : Manual handling Units come in flat pack boxes and as a whole unit can be heavy. There is a danger of musculoskeletal injury through incorrect lifting techniques and crush injuries if dropped on feet/hands.

Control Measures:

1. When lifting and moving whole or part units, be sure to use the correct lifting aids When moving or lifting part of units, ensure you use the correct manual handling techniques Wear the correct foot protection in case items are dropped on toes

Hazard : Repetitive Movements Units are put together with screws in predrilled holes. Learners are asked to use a screwdriver to do this, which may cause repetitive strain injuries.

Control Measures:

1. Take regular breaks whilst screwing the units together

Hazard : Untrained workers All learners are deemed untrained workers when they first come in to the centre and start new activities. All are susceptible to injuring themselves with tools and resources they haven't used before

Control Measures:

1. Make sure all learners attend health & safety training once a week and all risks are pointed out and control measures discussed and monitored.

| | |
|--|--------------------------------|
| Documents Associated with this Risk Assessment: | |
| Review Date : 06/11/2022 | Reviewer : Brendan Bell |